

City of Los Alamitos

Agenda Report Consent Calendar

April 21, 2014
Item No: 8E

To: Mayor Gerri L. Graham-Mejia & Members of the City Council

Via: Bret M. Plumlee, City Manager

From: David L. Hunt, City Engineer
Steven A. Mendoza, Director of Community Development

Subject: Approval of Plans and Specifications, and Authorization to Bid for Street Improvement Project (CIP No. 13/14-04)

Summary: This report recommends actions to begin facilitating the construction of the Business Area Street Improvement Project consisting of street improvements on Winners Circle from Katella Ave. to 800 feet south; Portal Drive from Katella Ave. to 900 feet north; Ball Road from Bloomfield St. to 250 feet west of Kaylor Ave.; Los Alamitos and Bradbury Way intersection; and sidewalk improvements on Cerritos Ave. from Coyote Creek Channel to Chestnut St.

Recommendation:

1. Approve the plans and specifications for the construction of the Business Area Street Improvement Project (CIP No. 13/14-04); and,
2. Authorize Staff to advertise and solicit bid proposals.

Background

The City of Los Alamitos proposes to resurface the following four streets and sidewalk improvements on one street:

- Winners Circle from Katella Ave. to 800 feet south
- Portal Drive from Katella Ave. to 900 feet north
- Ball Road from Bloomfield to 250 feet west of Kaylor Ave.
- Los Alamitos and Bradbury Way Intersection
- Cerritos Ave. sidewalk improvements from Coyote Creek Channel to Chestnut

The streets within the project limits will be ground and resurfaced with 2-inch thick Asphalt Rubber Hot Mix (ARHM), or removed and replaced with either Asphalt Concrete (AC) over Aggregate Base (AB). Visible cracks will be filled with rubberized crack filling

material. All manhole, water valve, anode and monitoring well covers within the project limits will be adjusted to grade. Existing curbs and driveways will be protected in place within the limits of the project. This project will also reinstall traffic striping, pavement markers, signing and install loop detectors at signalized intersections. Concrete sidewalks will replace the broken up asphalt sidewalks on the south side of Cerritos Ave to provide a safe entrance to the new Coyote Creek Park.

Discussion

Following is an approximate timeline for the completion of the Business Area Street Improvement Project:


- 4/21/14 Approval of plans & specifications by the City Council
- 4/29/14 Advertise project
- 5/29/14 Bid opening
- 6/16/14 Award of Contract
- 7/7/14 Start of construction
- 9/1/14 End of construction

Fiscal Impact

The construction estimate for the project is \$500,000 and the funding for this project is from three different 2013/2014 adopted budgets. Funding sources are from the Gas Tax, Traffic Improvement and Measure M funds. The budgeted numbers include design, construction management and construction.

- Ball Road, Portal and Winners Circle - \$600,000
- Los Alamitos Blvd. and Bradbury Intersection Pavement - \$40,000
- Cerritos Ave Sidewalk Project - \$60,000

Prepared By:



David L. Hunt, PE
City Engineer

Reviewed By:



Steven A. Mendoza
Community Development/Public Works Director

Fiscal Impact Reviewed By:



Glenn L. Steinbrink
Interim Administrative Services Director

Approved By:



Bret M. Plumlee
City Manager

Attachment: Plans and Specifications are available for review in the City Clerk's Office