

CITY OF LOS ALAMITOS

Addendum Number 2

PAVEMENT REHABILITATION IN GREENBROOK NEIHBORHOOD AND LITTLE
COTTONWOOD PARK
CIP 18/19-07

To all bidders under specifications for Request for Bids for the Construction of **Pavement Rehabilitation in Greenbrook Neighborhood and Little Cottonwood Park**, which are to be received by the City of Los Alamitos, until 11:00 A.M. on Tuesday, April 30, 2019:

The intent of this Addendum No. 2 is to modify the bid schedule and specifications.

I. In reference to the subject Project, the following modifications to the Contract Documents shall be included in the Bid:

1. The following revisions to the Special Provisions:

a. The following is hereby added to Section 302-5.9 Measurement and Payment:

Payment for removal of existing and construction of 3-inch thick full depth AC pavement shall be paid at the contract price per ton (TON) and include full compensation for all labor, materials, tools, equipment and incidentals required to remove existing and construct 3-Inch Thick AC pavement to the lines and grades shown on the plans. This bid item will include furnishing the material, placement, compaction, prime coat, asphaltic emulsion coating on vertical surfaces to abut the new pavement, grading and compaction of subgrade, and all other work required to result in an asphalt pavement meeting the requirements of the specifications.

II. The revised Bid Schedule B, included herewith this Addendum No. 2, replaces the original Bid Schedule B.

III. The Special Provisions shall be used in submitting bids, and an acknowledgment of receipt of this Addendum No. 2 shall be entered on Page 5 of the Bid Proposal. Failure to provide such acknowledgment shall render the bid as non-responsive and subject to rejection.

Date: April 29, 2019

BY ORDER OF THE CITY OF LOS ALAMITOS PUBLIC
WORKS DIVISION

By



David Hunt
City Engineer
City of Los Alamitos Public Works Division

13	CONSTRUCT TYPE II SLURRY SEAL.	9	TON	\$	\$
14	INSTALL SIGNING AND STRIPING COMPLETE PER PLANS.	1	LS	\$	\$
15	INSTALL INDUCTIVE LOOP DETECTORS	2	EA	\$	\$
Subtotal - Schedule A					

Bid Schedule Total (Schedule A) \$ _____

Bid Schedule Total (Schedule A) (in words):

SCHEDULE B					
LITTLE COTTONWOOD PARK PAVEMENT REHABILITATION					
No.	Item Description	Estimated Quantity	Unit	Unit Price	Item Amount
16	COLDMILL EXISTING AC PAVEMENT 1 INCH UNIFORM DEPTH	25,200	SF	\$	\$
17	CONSTRUCT 2-INCH THICK ASPHALT RUBBER HOT MIX (ARHM) OVERLAY	310	TON	\$	\$
18	REMOVE AND CONSTRUCT 3-INCH THICK AC	20 200	TON	\$	\$
19	REMOVE AND CONSTRUCT 4-INCH AGGREGATE BASE	13 130	CY	\$	\$
20	REMOVE AND REINSTALL WOOD FENCE	1	LS	\$	\$
21	INSTALL SIGNING AND STRIPING COMPLETE PER PLANS.	1	LS	\$	\$
22	INSTALL COURT SURFACING AND STRIPING COMPLETE PER PLANS.	1	LS	\$	\$
Subtotal - Schedule B					

Bid Schedule Total (Schedule B) \$ _____

Bid Schedule Total (Schedule B) (in words):

Grand Total (Schedule A + Schedule B) \$ _____

Grand Total (Schedule A + Schedule B) (in words):

The Contractor shall be responsible for calculating and providing unit prices for the schedule. The proposal schedule shall include all costs for services, labor, materials, equipment, and installation associated with completing the work in place per the plans, specifications and details.

For the purposes of determining the lowest responsible bidder, the Bid Schedule Total of Schedule A and Schedule B shall be considered.

(Company Name of Bidder)

(Date)